

To: 6 082470  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
290 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-12 15-163-19429-0001 222P  
API NUMBER 15- E-16,626

NW, SEC. 4, T 10 S, R 20 WE  
4950 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3258  
Operator: Lansing Energy Corporation  
Name & Address: 107 N. Market  
Suite 1115  
Wichita, Kansas 67202

Lease Name Hall Well # #3  
County Rooks 123.50  
Well Total Depth 3838 TD 3800' RTKCC feet  
Conductor Pipe: Size feet  
Surface Casing: Size 10 3/4" feet 355'

Abandoned Oil Well Gas Well Input Well X SWD Well X D&A  
RTKCC  
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 8:30A.M. Day: 12 Month: August Year: 19 91

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: Order 735 sks. of 65/35 posmix - 6% gel. - Run tubing to 3800' and spot  
100 sks. of common cement.

RECEIVED  
STATE CORPORATION COMMISSION  
8-23-91

AUG 23 1991

Shot hole at 1750', 960' & 800'. Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 8:00P.M. Day: 12 Month: August Year: 19 91

ACTUAL PLUGGING REPORT 10 3/4" set at 355' w/225 sks. 7" set at 3820' w/250 sks.

Top perf. at 3510'. Plugged bottom with 100 sks. common. Shot 4 holes and recovered  
700' of casing. Ran 2 3/8" tubing to 3750' and spotted 100 sks. common. Pulled tubing  
to 800' and spotted 65/35 posmix - 6% gel. to 1500' w/200 sks. Spotted cement to surface.  
Pulled all tubing and squeezed down 10 3/4" surface casing 435<sup>sks</sup> cement w/400 P.S.I.

Remarks: By: Allied. Ran Line to 3700'.  
(If additional description is necessary, use BACK of this form.)

I (Allied) hereby observe this plugging.

Signed Gilbert G. Scheck  
(TECHNICIAN) E.G.S.

INVOICED  
DATE 9-5-91  
INV. NO. 32942