

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03138-00-00  
Spot: CSWNENW Sec/Twnshp/Rge: 4-10S-20W  
4290 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: HALL Well Number: 4  
County: ROOKS Total Vertical Depth: 3812 feet

Operator License No.: 4472  
Op Name: N.F. PRODUCERS, INC.  
Address: 940 WADSWORTH - #300  
LAKEWOOD, CO 80215

Conductor Pipe: Size feet:  
Surface Casing: Size 10.75 feet: 372  
Production: Size feet:  
Liner: Size feet:

\$ 123.89

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/08/2001 12:30 PM  
Plug Co. License No.: 4472 Plug Co. Name: N.F. PRODUCERS, INC.  
Proposal Rcvd. from: DEAN IVES Company: N.F. PRODUCERS, INC. Phone: (785) 623-0967

Proposed 5 1/2" set at 3808'. PBTD 3300'.  
Plugging Perforated 2210' - 1760' - 960'.  
Method: Ordered out 285 sxs cement - 7 sxs gel spacer - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/08/2001 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2760'.  
Allied pumped 7 sxs gel spacer with 50 sxs 60/40 pozmix - 10% gel.  
Pulled tubing to 2140'.  
Allied pumped 160 sxs cement with 300# hulls - cement circulated.  
PTOH. Squeezed with 15 sxs.  
Max. P.S.I. 300#. S.I.P. 200#.  
Hooked up backside. Pumped 25 sxs cement with 100# hulls.  
Max. P.S.I. 350#. S.I.P. 350#.

RECEIVED  
8-14-01  
AUG 14 2001  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

INVOICE

DATE

8-15-01

Form CP-2/3

NO. REC

2002060235

AUG 13 2001

CONTINENTAL OIL COMPANY

#4

HALL

4-10-20W  
SW NE NW

Contr.

ROOKS

County

E 2229

Comm.

Comp.

5-27-49

IP

116 BOPD & 10 BW


PHY POT

| Tops | Depth | Datum |
|------|-------|-------|
| Awk  | 1735  | +494  |
|      |       |       |
| HEEB | 3462  |       |
|      |       |       |
| LANS | 3502  |       |
|      |       |       |
|      |       |       |
| ARB  | 3807  |       |
|      |       |       |
| T.O. | 3812  |       |

Casing

10" 372  
5" 3808

EST 3540-71; OP 1 HR  
 REC 300' MUD & 300' S WT  
 DEL 3810  
 SWB 3 1/2 BOPH / 4 HRS  
 ACID 500  
 SWB 28 BO / 24 HRS  
 DD 3812  
 SWB 21 BO & 1 1/2 BW / 8 HRS  
 SWB 30 BO & 1 1/2 BW / 12 HR



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

3/1 - 2229