

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03136-00-00
Spot: CSWNWNW Sec/Twnshp/Rge: 4-10S-20W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: HALL Well Number: 2
County: ROOKS Total Vertical Depth: 3836 feet

Operator License No.: 4472
Op Name: N.F. PRODUCERS, INC.
Address: 940 WADSWORTH - #300
LAKEWOOD, CO 80215

Conductor Pipe: Size feet:
Surface Casing: Size 10.75 feet: 360
Production: Size feet:
Liner: Size feet:

\$124.67

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/08/2001 8:00 AM
Plug Co. License No.: 4472 Plug Co. Name: N.F. PRODUCERS, INC.
Proposal Rcvd. from: DEAN IVES Company: N.F. PRODUCERS, INC. Phone: (675) 623-0967

Proposed Plugging Method: 6" set at 3834'. No records.
Top of fish 1080'. Fiberglass tubing in the hole.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/08/2001 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to top of fish at 1080'.
Allied pumped 180 sxs 60/40 pozmix - 10% gel, followed with 160 sxs 60/40 pozmix - 10% gel with 700# hulls.
Pulled tubing to 950'.
Allied pumped 110 sxs cement - circulated cement.
PTOH. Topped with 10 sxs.
Checked backside - pressured to 500#.

RECEIVED
8-14-01
AUG 14 2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 8-15-01

INV. NO. 2002060135

Form CP-2/3

AUG 13 2001

Continental Oil Co.

#2

Hall

4-10-20W

SW NY NY

Contr. KENTON DRILLING CO.

Hooker

County

E 2257 Comm 8-30-47 Comp 10-3-47 IP 1785 BOED & 30% WTR.

DEPTHO

Tops	Depth	Datum
Arh	1763	+494
LANS	3515	
ARB	3834	7577
T. D.	3836	

Casing
 10" 360
 6" 3834

2000' OIH, 1 hr
 Swb 70 BOPH/3 hrs

355
 85

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS