

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03135-00-00
Spot: CNENWNW Sec/Twnshp/Rge: 4-10S-20W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: HALL, KH Well Number: 1
County: ROOKS *PT KCC* Total Vertical Depth: 3833 feet

Operator License No.: 4472
Op Name: N.F. PRODUCERS, INC.
Address: 940 WADSWORTH - #300
LAKEWOOD, CO 80215

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 241
Production: Size 1 feet: 3828
Liner: Size _____ feet:

\$124.57

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/08/2001 4:00 PM
Plug Co. License No.: 4472 Plug Co. Name: N.F. PRODUCERS, INC.
Proposal Rcvd. from: DEAN IVES Company: N.F. PRODUCERS, INC. Phone: (785) 623-0967

Proposed Plugging Method: 7" at 3828'.
Perforated at 2225' - 1780' - 975'.
Run tubing to plug.
Ordered out 375 sxs cement - 16 sxs gel spacer - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/08/2001 9:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2760'.
Allied pumped 16 sxs gel spacer with 200# hulls, followed with 65 sxs 60/40 pozmix - 10% gel - 100# hulls.
Pulled tubing to 2100'.
Allied pumped 150 sxs cement with 200# hulls.
PTOH. Squeezed 80 sxs cement.
Max. P.S.I. 800#. S.I.P. 400#.
Backside pumped 50 sxs cement with 200# hulls.
Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED
8-14-01
AUG 14 2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams

(TECHNICIAN)

INVOICED

DATE 8-15-01

NO. 2002060235

Form CP-2/3

AUG 13 2001

CONTINENTAL OIL CO

#1 L H HALL

L-10-20W
NE NW NW

Cont'r

ROOKS County

E 22 1/4 Corn 6-17-44 Comp 7-11-44 IP 1489 BOPD


992 BW

Tops	Depth	Datum
ANH	1750	+494
LANS	3199	
CONO	3782	
STMP	3803	
ARB	3828	-1584
TD	3833	

Casing

10" 241
7" 3828

1000' OIH/2 hrs @ 3828-33



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS