

4-060558

8-10

15-163-04085-0001

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - N/A

NE NE NE /4 SEC. 05, 10 S, 20 W  
4620 4950 feet from S section line  
660-330 feet from E section line

RTKCC

Operator license# 31479

Lease ~~D.O.~~ Miller A well # 1

Operator: Pilot Oil, Inc.

County Rooks

Address: Box 651  
Hutchinson, Kansas 67504

Well total depth 3800 feet <sup>3836 RTKCC / 23.5<sup>-0</sup></sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 145 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Co Tools License#    

Address:    

Company to plug at: Hour: 1:00P.M. Day: 10 Month: August Year: 94

Plugging proposal received from: Chuck Schmidt

Company: Pilot Oil, Inc. Phone: 316-772-7117

Were: Order 350 sxs. 60/40 posmix - 10% gel and hulls.  
Plug with tubing.  
Lost packer with 1500' tubing in the hole.  
Emergency permission to plug with rig over the hole.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 4:30P.M., Day: 10, Month: August, Year: 94

Actual plugging report: 8 5/8" to 145'. 5 1/2" to 3800' w/300 sxs.  
Perforate at 970' - 1820' - 2260'. Ran tubing to 2250'+. Pumped 75 sxs.  
cement with 100# hulls. Pulled tubing to 1125'. Pumped 90 sxs. cement  
with 200# hulls with cement to surface. Pulled tubing. Tied onto  
annulus and pumped 35 sxs. cement with hulls. Tied onto production  
casing and pumped 15 sxs. cement. Pressured to 200# and blew out head.

STATE CORP. RECEIVED  
8-17-94  
AUG 17 1994

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD     BAD X Anhy. plug: YES X NO    

Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO    

Plugged through TUBING X, CASING    . Elevation:     GL

I did [X] did not [   ] observe the plugging.

Herb Deines

DH (agent)

Form CP-2/3

INVOICED  
DATE 8-26-94

INV. NO. 41031  
8-10 NOV 16 1994