

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03146-00-00
Spot: NESWNW Sec/Twnshp/Rge: 5-10S-20W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: RENNER Well Number: 5
County: ROOKS Total Vertical Depth: 3843 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3835
Surface Casing Size: 8.625 feet: ~~765~~
155

RT KCC

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/27/2003 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/27/2003 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 650' and 1675'.
TIH with tubing to 1675'.
Tied onto tubing - circulated cement with 155 sxs cement and 500# hulls.
POOH. Topped with 195 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.


RECEIVED
9-2-03
SEP 02 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

15-163-03146-0000

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

COPY


Company - LION OIL COMPANY
Farm - Renner No. 5

SEC. 5 T. 10 R. 20W
NE SW NW

Total Depth. 3843
Comm. 11-18-48 Comp. 11-29-48
Shot or Treated. 500 acid
Contractor. Glenn Peol Drilling Company
Issued. 1-8-49

County. Rooks

KANSAS



Elevation. _____

Production. Ech. pot. 2332

Figures Indicate Bottom of Formations.

sand, shale	155
shale, shells	880
sand, shale	1285
shale, sand	1765
anhydrite	1820
shale, shells	2255
lime, shale	2630
lime	2690
lime brkn	2745
limo, shale	3540
limo	3665
limo, shale	3843
Total depth	

Tops:

Arbuozle 3834

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1969
CONSERVATION DIVISION
Wichita, Kansas