

10-15-163-19430-0000
10-17

6 010689

API NUMBER 15- March 1951 D-2726

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SW, SEC. 5, T 10S, R 20 W/EXX
990 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5706

Lease Name Baldwin Well # 4 SWD

Operator: L and F Oil Operations

County Rooks 141.60

Name & Address Box 1435

Well Total Depth 4357 feet

Hays, Ks.

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 490

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor L and F Oil Operations License Number 5706

Address Same

Company to plug at: Hour: 9:30AM Day: 17 Month: Nov Year: 19 89

Plugging proposal received from Floyd Kelley

(company name) Same (phone)

were: Clean out to t.d., run tubing to t.d., spot 100 sks common cement pull tubing up the hole then circulate with 65/35 poz 6% gel, pull tubing and squeeze 5 1/2" casing w/65/35 poz 6% gel. Squeeze 8 5/8" w/65/35 poz 6% gel 5 1/2" casing at 3983'.

12-4-89

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2 PM Day: 17 Month: Oct. Year: 19 89

ACTUAL PLUGGING REPORT Cleaned out to 1480'. Ran tubint to 1480'.

Spotted 50 sks common cement, pulled tubing to 600'. spotted 50 sks cement and 25 sks 65/35 poz 6% gel. Pulled tubing, pumped down 5 1/2" 125 sks 65/35 poz 6% gel, 3 sks hulls max pres. 500#. Close 200#. Pumped down 8 5/8" 75 sks 65/35 poz 6% gel 2 sks hulls, Max 300#. Close 200#. All was witnessed by Gilbert Balthazor. Allied Cement Co. Checked Nov 20, 1989 by Gilbert Balthazor. Cement was to the top.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE DEC 08 1989

INV. NO. 26717

10-17

Gilbert Balthazor

Signed Dale F. Balthazor (TECHNICIAN)