

4-041455

4-23 15-163-19432-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 9-28-60

82 82 NW /4 SEC. 05, 10 S, 20 W  
2970 feet from S section line  
3960 feet from E section line

Operator license# 5465 Lease Renner well # 9

Operator: B-J Oil Company County Rooks

Address: 1503 Vine Well total depth 3833 feet <sup>124.57</sup>  
Suite B Conductor Pipe: 0 inch @ 0 feet  
Hays, Kansas 67601 Surface pipe 8 5/8 Inch @ 232 feet  
w/125

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#           

Address: Russell, Kansas 67665

Company to plug at: Hour: 11:00A.M Day: 23 Month: April Year: 93

Plugging proposal received from: J.B. Collins

Company: B-J Oil Company Phone:           

Were: 5 1/2" casing set @ 3838' w/650 sx. cement. Anhy. - Perf.  
@ 1790'. Dakota @ 985'. Perf. @ 230'. Ordered 300 sx. 60/40 pozmix -  
10% gel. with 1/4# F.C. plus 400# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All, Part[  ], None[  ]

Completed: Hour: 6:15P.M., Day: 23, Month: April, Year: 93

Actual plugging report: 5 1/2" casing.  
Spot bottom plug: 50 sx. cement @ 3200'.  
Spot 2nd. plug: 50 sx. cement w/200# hulls @ 2400'.  
Spot 3rd. plug: 50 sx. cement w/200# hulls @ 1750'.  
Spot 4th. plug: 100 sx. cement @ 985'.  
Circulated cement to surface and squeezed at surface.  
8 5/8" S.P. - circulate to surface from perf. @ 230'.  
Max. 700#. S.I. 300#.

Remarks:           

Condition of casing(in hole):GOOD  BAD  Anhy.plug:YES  NO   
Bottom plug(in place):YES  ,CALC  ,NO  Dakota plug:YES  ,NO   
Plugged through TUBING  , CASING  . Elevation:            GL           

I did / did not[  ] observe the plugging.

*Dennis L. Hamel*  
RECEIVED  
STATE CORPORATION COMMISSION  
6-9-93  
JUN 9 1993

(agent) CONSERVATION DIVISION  
Form CP-2/3 Wichita, Kansas

INVOICED  
DATE 6-11-93  
INV. NO. 37890  
4-23