

4- 041388

7-28

15-163-03148-0001

128 R

D-08,624

API number: 15- - 12-19-48

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C W2 NW NW /4 SEC. 05, 10 S, 20 W
4620 feet from S section line
4950 feet from E section line

Operator license# 5465

Lease Renner well # 7

Operator: B.J. Oil Company

County Rooks 125.32

Address: 1503 Vine
Hays, Kansas 67601

Well total depth 3856 feet PBTB 1700'
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 154 feet
w/150 sx.

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 7:00A.M. Day: 28 Month: July Year: 92

Plugging proposal received from: J.B. Collins

Company: B.J. Oil Company Phone:

Were: Perf. @ 1250' - 1290'. W.L.M. 1275'. 4 1/2" liner with cement
circulated to surface in annulus - 8 5/8".
Ordered 120 sxs. 60/40 pozmix - 8% gel. with 1/4# F.C. plus 100# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:45P.M., Day: 28, Month: July, Year: 92

Actual plugging report: Hooked-up to casing. Pumped in 20 sx. 60/40
pozmix - 8% gel. followed w/100 sx. 60/40 pozmix - 8% gel. with 100#
hulls. Max. 300#. S.I. 100#.

Remarks: Top of fluid 400'.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE 8-26-92

36038

OCT 28 1992

RECEIVED
STATE CORPORATION COM
4-10-92
AUG 10 1992
CONSERVATION DIVISION
Wichita, Kansas