

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03144-00-00  
Spot: NWSEW Sec/Twnshp/Rge: 5-10S-20W  
3630 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: RENNER Well Number: 2  
County: ROOKS Total Vertical Depth: 3835 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3826  
Surface Casing Size: 8.625 feet: 154

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/27/2003 1:00 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed  
Plugging  
Method:

Ordered out 125 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/27/2003 2:30 PM KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

Dug out well and found no production casing.  
RIH with polish rod on a sand line.  
Hit hard TD at 250'. Decided to P&A.  
Swaged onto 8 5/8" - mixed and pumped 125 sxs cement with 400# hulls.  
S.I.P. 350#


RECEIVED  
9-2-03  
SEP 02 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

LION OIL COMPANY

#2

RENNER

5-10-20W

NW SE NW

Contr. GLENN W. PEEL DRILLING CO.

ROOKS

County

E 2257

Comm.

Comp. 11-12-48

IP 3000 BOPD.

| Tops     | Depth | Datum | Casing                 |
|----------|-------|-------|------------------------|
|          |       |       | 8" 15L ACIC 500        |
|          |       |       | 5" 3826 SWB 86 80/1 HR |
| LANS     | 352L  |       |                        |
| CCNG     | 3786  |       |                        |
| SIMP SH  | 3805  |       |                        |
| SIMP DOL | 3812  |       |                        |
| ARB      | 382L  |       |                        |
| T.D.     | 3835  |       |                        |

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg. Wichita, Kansas


COPY  
15-163-03144-0000

Company - LION OIL COMPANY  
Farm - Renner No. 2

SEC. 5 T. 10 R. 20W  
NW SE NW

Total Depth. 3835'  
Comm. 10-10-48 Comp. 10-20-48  
Shot or Treated. Acidized W/500 Gals.  
Contractor. Glenn Peol Drlg. Co., Inc.  
Issued. 12-4-48

County. Rooks  
KANSAS



Elevation. \_\_\_\_\_

Production. Echo. Pot. 5600 Bbls.

Figures Indicate Bottom of Formations.

|                      |      |
|----------------------|------|
| surface sand & clay  | 85   |
| shale                | 153  |
| shale, shells & sand | 1155 |
| sand & shale         | 1490 |
| shale & shells       | 2195 |
| lime & shale         | 2640 |
| lime                 | 2685 |
| lime & shale         | 3215 |
| shale                | 3290 |
| lime                 | 3345 |
| lime & shale         | 3380 |
| lime                 | 3430 |
| lime & shale         | 3480 |
| lime                 | 3805 |
| shale & lime         | 3825 |
| dolomite RTD         | 3828 |
| dolomite             | 3835 |
| Total Depth          |      |

Tops:  
Arbuckle 3826

Swab 86 BO in 1 hr.  
Echo-meter Pot. 5600 BOPD

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 19 1969  
CONSERVATION DIVISION  
Wichita, Kansas