

7-13

4-042020

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-02,020-0000

NE NW SW / 4 SEC. 05, 10 S, 20 W
2310 feet from S section line
4290 feet from E section line

Operator license# 5386

Lease: Baldwin Well # 2

Operator: Production Drilling, Inc.

County: Rooks

Address: P.O. Box 680
Hays, Kansas 67601

Well total depth 3908 ^{127.01} feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 1778 Feet
W/N/A sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Swift Services License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: 8:00 A.M. Day: 13 Month: July Year: 1999

Plugging proposal received from: Gaylord Burroughs

Company: Production Drilling, Inc. Phone: -

Were: Ordered 300 sxs Swift Lite plus 700# hulls.
5 1/2" casing set at 3908' w/N/A sxs cement.
Perfs at 3836' - 3849'.
Perf Salt at 2225'; Anhy at 1800'; Dakota at 1000'; T.O.F. N/A.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:30 P.M. Day: 13 Month: July Year: 1999

Actual plugging report: (Casing cap 94 bbls) Hooked-up cementers to 5 1/2" casing - squeezed casing with 200 sxs cement with 600# hulls (115 bbls slurry) Max. P.S.I. 700#. Squeezed 8 5/8" S.P. with 70 sxs cement plus 100# hulls. (40 bbls slurry) Max. P.S.I. 400#.

Remarks:
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC X, NO
Plugged through TUBING CASING X. Elevation: G.L.

I did [X] / did not [] observe the plugging.

INVOICED
DATE 8-18-99
INV. NO. 60239

RECEIVED (agent)
8-13-99
AUG 13 1999
STATE CORPORATION COMMISSION Form CP-2/3
CONSERVATION DIVISION
Wichita, Kansas

(R)