

4-042016

7-13

D-22,332

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-19,000-000

NE NE SW /4 SEC. 05, 10 S, 20 W  
2310 feet from S section line  
2970 feet from E section line

Operator license# 5386

Lease: Baldwin Well # 1

Operator: Production Drilling, Inc.

County: Rooks 125.78

Address: P.O. Box 680  
Hays, Kansas 67601

Well total depth 3870 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 1304 Feet  
W/600 sxs.cmt.

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Swift Services

License# 32382

Address: Ness City, Kansas 67560

Company to plug at: Hour: 8:00 A.M. Day: 13 Month: July Year: 1999

Plugging proposal received from: Gaylord Burroughs

Company: Production Drilling, Inc. Phone: -

Were: Ordered 90 sxs Swift Lite with 1/4# F.C. plus 500# hulls.  
5 1/2" casing set at 3863' w/150 sxs cement.  
Perfs at 1240' - 1300'.  
Plug back to anhy - casing cemented from anhy to surface.

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:15 P.M. , Day 13, Month: July, Year: 1999

Actual plugging report: Hooked-up cementers to 5 1/2" casing - squeezed 90 sxs cement with 500# hulls mixed in cement. Pressured-up to 1500#. Checked 8 5/8" S.P. Cement visible at surface.

Remarks: Casing cap 32 bbls-pumped 52 bbls slurry.  
Condition of casing(in hole): GOOD X BAD  
Any plug: YES X NO  
Bottom plug(in place): YES, CALC X, NO  
Dakota plug: YES X, NO  
Plugged through TUBING CASING X. Elevation: G.L.

I did [ X ] / did not [ ] observe the plugging.

Dennis Hamel (agent)

INVOICED

DATE 8-18-99

WV. NO. 60239

RECEIVED STATE CORPORATION COMMISSION

8-13-99  
AUG 13 1999

CONSERVATION DIVISION  
Wichita, Kansas

Form CP-2/3

(R)