

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-30151-00-00  
Spot: CNWNESW Sec/Twnshp/Rge: 7-10S-20W  
2310 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: TEMPLE Well Number: 2  
County: ROOKS Total Vertical Depth: 3862 feet

Operator License No.: 4952  
Op Name: SCHLOBOHM, STARR F.  
Address: 47 MICHAWANIC ROAD #3D  
SANBORNVILLE, NH 03872

Conductor Pipe: Size feet: 8 125.52  
Surface Casing: Size 8.625 feet: 174  
Production: Size 5.5 feet: 3853  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/15/2002 9:00 AM  
Plug Co. License No.: 4952 Plug Co. Name: SCHLOBOHM, STARR F.  
Proposal Rcvd. from: JOHN DRISCOLL Company: SCHLOBOHM, STARR F. Phone: (785) 483-9580

Proposed 5 1/2" set at 3853'.  
Plugging D.V. Tool at 1740' with 515 sxs.  
Method: Fluid Level at 1900'.  
Ordered out 350 sxs 60/40 pozmix.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 02/15/2002 9:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 290 sxs 60/40 pozmix - 10% gel with 400# hulls.  
Max. P.S.I. 800#. S.I.P. 600#.  
8 5/8" instant pressure 400# (two staged).

RECEIVED  
KANSAS CORPORATION COMMISSION  
2-22-02  
FEB 22 2002  
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams  
(TECHNICIAN)

102

FEB 20 2002

INVOICED  
DATE Feb 25-02  
NO. 2002061408

Form CP-2/3

1-163

Map No.

OPER BOWMAN OIL COMPANY

Natoma, Kansas

WELL #2 TEMPLE


CONTR L.J. Dreiling, Inc.

FIELD Cooper Field (Lans &amp; Arb)

I.P. P 30 BOPD-NW, Arb 3381-33 &amp; 3853-59

DST #1 (Arb) 3832-47, Op 1 hr, 420' GIP, R 1380' oil &  
300' mdy oil, ISIP 672#/30", FP's 180-632#, FSIP  
646#/30"

DST #2 (Arb) 3847-59, Op 1 hr, 180' GIP, R 660' oil &  
420' mdy oil, ISIP 698#/30", FP's 81-454#, FSIP 685#/30"  
RTD 3862, Log, 5 1/2" @3853 w/125 sx. - CO 3859 TD, 8/3831-  
33 (Arb) FU 1950 oil, NW/12 hrs, nat, POP, P 30 BOPD NW,  
Arb 3831-33 & 3853-59 - COMPLETED on 1-17-66



S-T-R 7-10S-20W

SPOT NW NE SW

CO ROOKS, Ks.

ELEV 2262 KB

(KB Log)

Anh	1748	+ 514
Top	3294	-1032
Hb	3496	-1234
Tor	3517	-1255
Lan	3534	-1272
BKc	3754	-1492
Cg	3806	-1544
Sp dol	3816	-1554
Arb dol	3830	-1568
LTD	3859	-1597
RTD	3862	-1600
(Sp1)		
Anh	1742	
B/Anh	1787	
RTD	3862	

MISCEL DATA

GEOL Francis Whisler

ELEV 2260 DF

SPUD DATE 1-3-66

FTG

2257 GR

DRLG COMP

SUPPT

FR by DATA 12-21-65

CSG 8" @174' w/100 Sx.

5" @3853' w/125 Sx.

COMP by " 1-20-66