

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02029-00-00  
Spot: CNENESW Sec/Twnshp/Rge: 7-10S-20W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: TEMPLE Well Number: 1  
County: ROOKS Total Vertical Depth: 3869 feet

Operator License No.: 4952  
Op Name: SCHLOBOHM, STARR F.  
Address: 47 MICHAWANIC ROAD #3D  
SANBORNVILLE, NH 03872

Conductor Pipe: Size feet: 8 1/25.74  
Surface Casing: Size feet:  
Production: Size 5.5 feet: 3859  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/15/2002 10:30 AM

Plug Co. License No.: 4952 Plug Co. Name: SCHLOBOHM, STARR F.

Proposal Rcvd. from: JOHN DRISCOLL Company: SCHLOBOHM, STARR F. Phone: (785) 483-9580

Proposed Plugging Method: No squeeze records. Perforated 1800' and 1000'.  
Fluid 1500' from surface.  
5 1/2" set at 3859'. Open hole TD 3870'.  
Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 02/15/2002 12:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 1800' and 1000'.  
Ran tubing to 2000'.  
Allied pumped 175 sxs with 250# hulls. Lost circulation.  
Pulled tubing to 1600'.  
Allied pumped 125 sxs with 200# hulls. Cement circulated.  
PTOH. Cement down 200'. Ran out of cement - will top off.  
Hooked up to 8 5/8" and pressured up to 300#.  
Allied pumped 50 sxs with 50# hulls. S.I.P. 100#.  
02-19-2002 - Topped 5 1/2" casing with 80 sxs. Completed at 2:00 PM.

2-28-02 RECEIVED  
FEB 28 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

Feb 28-02

INV. NO.

2002061428

FEB 20 2002

REPUBLIC NAT'L GAS CO

#1

TEMPLE

7-10-20W  
NE NE SW


Contr. \_\_\_\_\_ ROOKS \_\_\_\_\_ County

E. 2264 .RB Comm. \_\_\_\_\_ Comp. 12-14-51 IP 200 BOPD  
PHY. POT

Tops	Depth	Datum
ANH	1745	519
HEEB	3504	-1240
ARB	3858	-1594
T.D.	3866	-1602

Casing  
 5 1/2" 3859 DST 3570-3650, 1/2 HR,  
 825' S WTR  
 DST 3858-66, 30 MIN,  
 600' OIL  
 DP: SWB 6 BOPH: ACID  
 350: DD 3869: SWB 5.4  
 BOPH

PALCO SW POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS