

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 17-31

LOCATION CS 1/2 SW NW

SEC. 2 TWP. 10 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Marcotte

Operator Francis Oil & Gas Address 905 Palace Bldg Tulsa,

Field _____ County Rooks

Total Depth ~~3855~~ 3885 Feet.

Plugging Contractor ~~Ace Pipe Pulling Co~~ Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 167' circulated with cement - 5 1/2" at 3885' with 125

sax cement behind - P.B. to 3848', perforated at 3840',

Filled with chat to 3830', set 4 sax cement with dump, bailer,

pulled 3110' 5 1/2" - mud to 165', set rock and 15 sax cement,

mud to 40', set rock and 10 sax cement to bottom cellar.

REC-11
STATE CORP. COM.
12-2-55

District Conservation Agent
11-30-55

Date _____

PLUGGING
FILE REC-2 710 P 200
BOOK PAGE 12 LINE 21

CONSERVATION DIVISION
WICHITA, KANSAS