

15-163-30041-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
7-24-67
JUL 24 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Leo J. Dreiling Oil Company

Complete Address: R. R. # 2 Victoria, Kansas

Lease Name Coddington Well No. 1

Location C W/2 NW ^{SE} ~~DW~~ R. R. # 2 Sec. 2 Twp. 10 Rge. 20 (E) X (W)

County Rooks Total Depth 3835

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Co. Tools Sun Cementing Co.

Address: Hays, Kansas License No.

Operation Completed: Hour 11:45 A Day 22 Month 7 Year 1967

The Above well was plugged as follows:

Total Depth 3835 8 5/8 csg set at 187' cwc 100 sc.

5 1/2 csg set at 3823' cw 100 sc cement.

DV tool set at 1723 and circ. to surface with cement.

No Pipe Recovered

Pumped 15 sc cem. and 28 sc gel down 5 1/2 csg. pres. 1000 lbs.

Filled (85/8-5 1/2) annulus with 15 sc cement.

Squeezed 5 1/2 csg thru plg container with 85 sc cement and shutin. Pres 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/24/67

INV. NO. 6019-U