

15-163-00635-0000

Form CP-3
Rev. 6-4-68

KANSAS

Y STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1973
08-09-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name K & G Oil Company
Complete Address Box 368 Plainville, Kansas 67663
Lease Name Sparks Well No. B-1
Location NE NE SW Sec. 2 Twp. 10 Rge. (E) (W) 20
County Rooks Total Depth 3838'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Kelso Pipe Pulling
Address Box 176 Chase, Kansas 67524 License No. 683
Operation Completed: Hour 11:30 A Day 8 Month 8 Year 1973

The above well was plugged as follows:

Total Depth 3838' 8 5/8 csg set at 168' cwc 140 sk.
5 1/2 csg set at 3828' cw 125 sk cmt.
Filled 5 1/2 csg W/sd (3800-3838) Dumped 5 sk cmt W/dump bailer. (3765-3800)
Cutoff and recovered 812' of 5 1/2 csg.
Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls, released 8 5/8 plug
and pumped 100 sk cmt. by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo L. Massey
Well Plugging Supervisor

INVOICED

DATE 8/9/73
INV. NO. 7747-W