

16
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-5-63
DEC 5 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 1130 Wichita Plaza Wichita, Kansas

Lease Name Glick Well No. 5

Location SE NE SE Sec. 4 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3786

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 10AM Day 4 Month 12 Year 63

The Above well was plugged as follows:

8 5/8" 144' circulated with cement - 5 1/2" 3785' with 125 sax cement.

Sand back to 3770', set 4 sax cement with dump bailer - pulled 720' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" - hole pressured up - pulled pipe to 400' and broke circulation - displaced 20 sax cement through 5 1/2" at 400', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180' heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Southwest Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/5/63
8241-u
INV. NO. _____

Signed: E. J. Petty
Well-Plugging Supervisor