

15-163-02017-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
12-5-63  
DEC 5 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 1130 Wichita Plaza Wichita, Kansas

Lease Name Glick Well No. 7

Location W $\frac{1}{2}$  NW ~~SE~~ Sec. 4 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3858

Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 11Am Day 12 Month 5 Year 62

The Above well was plugged as follows:

8 5/8" 175' circulated with cement - 5 1/2" 3849' with 100 sax cement & squeezed in Dakota section - amount cement ? - 4 1/2" liner set at 1500' and circulated with cement to 0'

Pumped 30 sax gel mud - pumped wiper plug followed by 50 sax cement - cement over-balanced and went down hole - openended 45 more sax cement in hole filling to 0' - welded clamp on between 5 1/2" at 8 5/8" and pumped 15 sax gel mud and 5 sax cement down ~~annulus~~ annulus of 5 1/2" and 8 5/8" - 200# pump pressure

Mudding and cementing by Southwest Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 12/5/62  
INV. NO. 8240-w

Signed: Edon Kelly  
Well Plugging Supervisor