

15-163 - 02018 - 0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
4-28-70
APR 28 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply, Inc.

Complete Address Box 169 Russell, Kansas 67665

Lease Name Towns Well No. 1

Location C E/2 NE SW Sec. 4 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3839

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lynch Casing Pulling, Co.

Address Great Bend, Kansas License No. 457

Operation Completed: Hour 4:30P Day 24 Month 4 Year 1970

The above well was plugged as follows:

Total Depth 3839' 8 5/8 csg set at 141' cwc

5 1/2 csg set at 3836' cw 150 sk cmt.

5 1/2 csg squeezed thru Dakato section.

Filled 5 1/2 csg W/sd (3800-3839) Dumped 5 sk cmt W/dump bailer. (3760-3800)

Shotoff and recovered 611' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 14 sk gel W/3 sk hulls—50 sk poz 6%—6 sk gel plug and 50 sk poz 6%.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo A. Massey
Well Plugging Supervisor

INVOICED

DATE 4/28/70
INV. NO. 1804-W