

15-163-00680-0000

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
6-22-60
JUN 22 1960

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks

Location: CS $\frac{1}{2}$ S $\frac{1}{2}$ NE Sec. 3 Twp. 10 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3863

I have this date completed supervision of plugging of:

Lease Name: Nutsch Well No. B-1

Operator's Full Name: Francis Oil & Gas

Complete Address: 905 Palace Bldg Tulsa, Okla

Plugging Contractor: Ace Pipe Pulling & Globe Cementing Co

Address: Great Bend, Kans License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5 PM Day 20 19 60 Month 6 Year 60

The above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" 3843' with 125 sax cement.

Filled with sand to 3830', set 4 sax cement with dump bailer, pulled

1400' 5 1/2" to 500', circulated hole with heavy mud (35 sax Gel), displaced

20 sax cement through 5 1/2" at 500', heavy mud to 170', displaced 20 sax

cement through 5 1/2" at 170', heavy mud to 35', and filled with cement

35' to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: *Edson Perry*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

INVOICED
DATE 6/24/60
INV. NO. 1537-W