

15-163-02022-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1974

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name L & F Oil Operators

Complete Address Box 415 Plainville, Kansas 67663

Lease Name W. E. Baldwin Well No. 5

Location S/2 NW SW Sec. 5 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3887'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Chas. Crowe Csg Pulling

Address Box 706 Hays, Kansas 67601 License No. 733

Operation Completed: Hour 3: P Day 30 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 3887' 10 3/4 csg set at 186' cwc 150 sk.

5 1/2 csg set at 3887' cw 100 sk cmt.

Set 5 1/2 wood plug at 2000' -dumped 4 sk cmt W/dump bailer. (2000-1970)

Cutoff & recovered 840' of 5 1/2 csg.

Mixed & pumped down 10 3/4 csg with 15 sk gel & water W/300 lbs hulls -50 sk

cmt -15 sk gel & water -released plug & 60 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing  
Well Plugging Supervisor

DATE 1/6/75  
INV. NO. 580-W