

15-163-03287-0000

Form CP-3  
Rev. 6-4-68

74

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
9-8-69  
SEP 8 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Bovaird Supply Company

Complete Address Box 2590 Tulsa, Oklahoma 74101

Lease Name Renner Well No. 8

Location SW NE NW Sec. 5 Twp. 10 Rge. (E) (W)20

County Rooks Total Depth 3823

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address Ellinwood, Kansas License No. 396

Operation Completed: Hour 1P Day 6 Month 9 Year 1969

The above well was plugged as follows:

Total Depth 3823' 8 5/8 csg set at 194' cwc

5 1/2 csg set at 3820' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3800-3823) Dumped 5 sk cmt W/dump bailer. (3760-3800)

Dakato squeezed. Cutoff and recovered 270' of 5 1/2 csg.

Mud to 700'. Set 5 1/2 plug, 5' rk & 10' sand. (685-700)

Mud to 270' set rock bridge (250-270)

Filled with 4 yds readymix cmt. (0-250)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/8/69  
INV. NO. 432-W

Signed: Leo A. Murray  
Well Plugging Supervisor