

15-163-04264-0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-6-61
JAN 6 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks
Location: NW NW SE Sec. 5 Twp. 10 Rge. 20 (E) (W)
Name of Field: _____ Total Depth: 3851

I have this date completed supervision of plugging of:

Lease Name: Beinke Well No. 1

Operator's Full Name: Leslie Oil Co

Complete Address: 542 Pet Bldg Wichita, Kansas

Plugging Contractor: Halliburton Cementing Co

Address: Hays, Kansas License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 30 Month 12 Year 60

The above well was plugged as follows:

8 5/8" 413' circulated with cement - 5 1/2" 3846' with 150 sax cement - PB
to 3576', perforated 3509' - squeezed at 1100' with 250 and 65 sax cement
(no pipe recovery)

Pumped hole full heavy mud (40 sax Gel), pumped cementing plug, followed
by 65 sax cement - cement 525' to 0',

Mudding and cementing by Halliburton Co *700# to 500# pump pressure

Signed: Edwin Petty
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 1/11/61
INV. NO. 2503-W