


KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-NA- 

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name L & F Oil Operations

Complete Address Box 415 Plainville, Kansas 67663

Lease Name W. E. Baldwin Well No. #8

Location NNW5W Sec. 5 Twp. 10 Rge. 20 (East) (West)

County Rooks Total Depth 3775

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D&A     

Other well as hereinafter indicated     

Plugging Contractor Kelso Casing Box 176

Address Chase, Ks 67524 License No. 683

Operation Completed: Hour: 12:30 PM Day: 19 Month: 5 Year: 19 82

Plugging Operations attended by Agent?: All X Part      None     

The above well was plugged as follows:

10 3/4" @ 208' w/circ cement - 4 1/2" @ 3774' w/ 25 sy  
Topper 3744' - cast Plug @ 3700' w/50' sand & 4 sy cement.  
Recovered 1000' of 4 1/2" casing - Ordered 160 sy 50/50 poz mix 6% gel,  
38 cc, 20 sy gel, 5 sy hulls & pumped in 4 hulls ->  
12 gel -> 1 hull -> 70 cmt -> 8 gel -> 90 cmt.

RECEIVED  
STATE CORPORATION COMMISSION

6-1-82

JUN 1 1982

(Allied)

Max P.S.F. 500 #

Amount of Surface Casing: 208'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_

Conservation Division Agent

6-3-82

349-u