

15-163-20336-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
12-17-70
DEC 17 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Company
Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas
Lease Name Nutsch "B" Well No. 5
Location SE SE NW Sec. 3 Twp. 10 Rge. (E) (W) 20
County Rooks Total Depth 3819'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Gabbert & Jones Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 11:30 A Day 14 Month 12 Year 1970

The above well was plugged as follows:

RTD 3819' 8 5/8 csg set at 249' cwc 170 sk. Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Meaney
Well Plugging Supervisor

DATE: 12/17/70
INV. NO. 3040-W