

KCC OIL/GAS REGULATORY OFFICE

Date 9/16/09 thru 9/28/09

- New Situation
- Response to Request
- Follow-up

Operator license # 32158

Operator H & B Petroleum Corp

Address P.O. Box 277
Ellinwood, Ks 67526

Location E1/2 SW SE, Sec 18, T 22S, R 33 W

Lease Garden City Well # A 6

County Finney

Operator phone number 620-564-3002

API # 15-055-22046-0000

Reason for Investigation: Alternate II Cementing

Problem: _____

Person(s) Contacted: _____

Findings: 8 5/8" 456' ; 5 1/2" 4826 w/ 100 sx

Port Collar 4' 1941' TD 4840'

Allied cemented thru port collar using 150sx 60/40 Pz
8% gel followed by 50sx CIA Common cmt. No blow or circulation
up 5 1/2 x 8 5/8 annulus. Will run cmt bond log & migrate to raise cmt
9/24/09 Bond log indicated all the cement went down. Perf 4 hrs @ 1150'. Brkdn @ 1000'
Pumped 200sx 60/40 Pz 8% gel & 50sx CIA. Circ 55sx to pit
9/28/09 Log Tech ran Gamma Ray CBL from 1250' to 0'. TOC % 136' F.S.
 photos taken: _____

Action/Recommendations: Alternate II Cementing Satisfactory

RECEIVED

OCT 15 2009

KCC WICHITA

- Lease Inspection
- Complaint
- Field Report

By Ken Schulte
PART II

Retain 1 copy Joint District Office.
Send one copy Conservation Division

- RBDMS
- KGS
- District files
- TA program
- T-1 database
- Courthouse

