



15-051-22613-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Jim Mortinger of C&R Drilling Company has this date requested permission to plug the following described well:

Operator's Full Name: Dreiling L.T.D. of Colorado

Complete Address: 410-17th St., Suite #1140, Denver, Colorado 80202

Lease Name: Dickinson Well No. #2-15

Location: NW SE NW Sec. 15 Twp. 12 Rge. 16 (E) (W)

County: Ellis Total Depth: 3441'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Mortinger was instructed to plug the well as follows:

8 5/8"-197' s.p. cuc. w/110 sacks common-2% Gel.-3% Cal. Cl.

Ordered 135 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 660' w/70sacks cement

2nd plug @ 200' w/40sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole and 5 sacks of cement in mouse hole

Very truly yours,

[Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

1-25-1982
JAN 25 1982

CONSERVATION DIVISION
Wichita, Kansas