



15-051-20867-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1972
12-26-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weiler of Shields Drlg. has this
date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Ks.

Lease Name: Chrisler "C" Well No. 1

Location: SE NE NW Sec. 16 Twp. 12 Rge. (E)(W) 16

County: Ellis Total Depth 3470' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weiler was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace

50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent