



15-051-20324-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 2-26-1968  
 SEP 26 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Damme of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Damme guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 1515 Wichita Plaza Wichita, Kansas

Lease Name: Windholz Well No. 1

Location: NE NE NE Sec. 17 Twp. 12 Rge. 16(E)(W) X

County: Ellis Total Depth 3489' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Damme was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace

50 sc cement thru drill pipe. Heavy mud to 200' set cementing plug and

displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

Leo F. Messing  
 Conservation Division Agent