

State of Kansas



15-051-22611-00-00

FORM CP-2

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Steve Fowler of Ramco Drilling Corp. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Samson Resources Company

Complete Address: 2700 First Place, Tulsa, Okla. 74103

Lease Name: Dodge Well No. #1-23

Location: SW/NE/NE Sec. 29 Twp. 12 Rge. 16 (E) (W)

County: Ellis Total Depth: 3659'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Steve Fowler was instructed to plug the well as follows:

8 5/8"-309' sp. cuc. w/200 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel-3% Cal. Cl. and 8 5/8" plug. Spotted with drill stem with heavy mud between all plugs.

1st plug @ 680' w/70 sacks cement

2nd plug @ 270' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole.

Very truly yours,

10-19-1981  
CONSERVATION DIVISION  
Wichita, Kansas

*[Signature]*  
Conservation Division Agent