



15-051-2013-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

12-13-1967
DEC 13 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sheppard of Sterling Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Sheppard guarantees payment of the plugging fee.

Operator's full Name: Sterling Drlg Co. & The Ballard & Cordell Corp.

Complete Address: P. O. Box 129 Sterling, Ks. 67579

Lease Name: Dickinson "A" Well No. 1

Location: NW SE SE Sec. 29 Twp. 12 Rge. 16 (E)(W) X

County: Ellis Total Depth 3565 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sheppard was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace
100 sc cement thru drill pipe. Heavy mud to 250' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with
2 sc cement.

Very truly yours,

Leo F. Mansel
Conservation Division Agent