

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-10061-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 4-23S-33W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: GARRY Well #: 2
County: FINNEY Total Vertical Depth: 4870 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1110		
CIBP		4400		WITH 2 SX CMT
SURF	8.625	375		WITH 275 SX CMT 158.28
PROD	4.5	4870	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2009 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BRIAN MEYER Company: HARTMAN OIL Phone: (620) 636-2090

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2009 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 4400' & 2 SX CMT. 2ND PLUG SET CIBP @ 1110'. TEST CASING TO 800#. 3RD PLUG PERFORATE 4 HOLES @ 1060'. PUMPED 80 SX CMT - 200# HULLS & 135 SX CMT SHUT IN PRESSURE 700#. 4TH PLUG PUMPED 65 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. SHUT IN PRESSURE 150#. 5TH PLUG REFILLED 4 1/2" CASING WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4746	4758		
4456	4462		


RECEIVED
SEP 21 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

SEP - 9 2009

KCC DODGE CITY

Form CP-27

10-19-09
2010060402