

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-21079-00-00
Spot: SENWSW Sec/Twnshp/Rge: 21-4S-26W
1420 feet from S Section Line, 1250 feet from W Section Line
Lease Name: MILISSA- ABBIE UNIT Well #: 21-1
County: DECATUR Total Vertical Depth: 3774 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 9915 W 21ST ST, STE B
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		

122.66

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/08/2009 6:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LARRY PICKNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: NONE
Date/Time Plugging Completed: 09/08/2009 7:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st. Plug at 2140' w/25 sxs.
2nd. Plug at 1350' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

10-20-09
2010060404

RECEIVED
SEP 21 2009
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Darrel Dipman (TECHNICIAN) CM