

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05167-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 3-15S-12W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SOUKUP Well #: 6
County: RUSSELL Total Vertical Depth: 3295 feet

Operator License No.: 31369
Op Name: GINTHER, KELLY DBA KAY DEE OIL
Address: 112 CINDY DR
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	722	0	w/unknown sxs cmt
L1	5.5	2995	0	
PROD	7	2958	0	w/unknown sxs cmt

107.09

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/17/2009 9:15 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: KELLY GINTHER Company: KAY DEE OIL Phone: (785) 483-5508

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls - 19 sxs gel.
Perf: 1500' - 715' - 150'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2009 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 3000' - pumped 19 sxs gel - followed with 75 sxs cement with 300# hulls mixed in.
Pulled tubing to 700' - pumped 100 sxs cement - cement circulated out 7" casing - closed 7" off.
Pumped 40 sxs cement - circulated cement out of the Braden head.
POOH. Topped off with 10 sxs cement.

10-20-09
2010060405

RECEIVED
SEP 21 2009
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3789.

Plugged through: TBG

District: 04

Signed

R. A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

SEP 18 2009

PHIL HAN OIL CO

#6

SOUKUP

3-15-12W
SW NW SW

Contr.

RUSSELL

County

E 1835 Comm. 1-21-47 Comp. 3-28-47 IP 250 BOPD & 40% WTR

Tops	Depth	Datum
ANHY	712	or 722
LANS	2969	
TD	3060	

Casing

10" 722


7" 2958

SO 2830-40, 700' OIH/2½ hr
A/10,000

Pmp 98 BO/13 hrs

Pmp 91 BO/7½ hrs

5" lnr @ 3048

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS