

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC
PCT
GPS

API Well Number: 15-119-20147-00-00

Spot: NWNW

Sec/Twnshp/Rge: 11-33S-29W

617 feet from N Section Line,

703 feet from W Section Line

Lease Name: BERGHAUS - A

Well #: 1

County: MEADE

Total Vertical Depth: 5772 feet

Operator License No.: 5086

String Size Depth (ft) Pulled (ft) Comments

Op Name: PINTAIL PETROLEUM, LTD.

SURF 8.625 1479 WITH 700 SX CMT

Address: 225 N MARKET STE 300
WICHITA, KS 67202

PROD 4.5 5768 1500 WITH 150 SX CMT **187.59**

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/14/2009 11:40 AM

Plug Co. License No.: 31627

Plug Co. Name: WHITETAIL CRUDE, INC

Proposal Rcvd. from: MIKE FRITZLER

Company: WHITETAIL CRUDE, INC

Phone: (785) 798-3641

Proposed Plugging Method: SAND TO 5584' & 4 SX CMT. PLUG AT 1500' WITH 10 SX GEL & 50 SX CMT. PLUG AT 510' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: JERRY W. STAPLETON

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/14/2009 1:15 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SANDED TO 5584' WITH 4 SX CMT. 1ST PLUG AT 1500' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. 3RD PLUG AT 180' WITH 25 SX CMT. CMT CIRCULATED.

Top Bot Thru Comments
5684 5687

RECEIVED
SEP 21 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

10-20-09
2010060414

Plugged through: CSG

District: 01

RECEIVED

SEP 15 2009

KCC DODGE CITY

Signed

Eric MacLaren

(TECHNICIAN)

Form CP-28