

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24217-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 31-30S-8E
2217 feet from S Section Line, 3696 feet from E Section Line
Lease Name: FERGUSON RANCH Well #: 11-31
County: COWLEY Total Vertical Depth: 3000 feet

Operator License No.: 33867

Op Name: PLANET GAS RESOURCES, LLC

Address: 250 auditora st
2919 E BROADWAY STE 309 TUCSON AZ

DENVER, CO 80220 TUCSON AZ 85176

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	464		225 SX
PROD	4.5	3000		300 SX

97.50

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 09/01/2009 8:00 AM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: JOE SAMUELS, HURRICAN

Company: HURRICANE SERVICES

Phone: (620) 437-2661

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 09/01/2009 1:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE W/CIBP AND SET @ 2564', DUMP BAILED 2 SXS CEMENT ON TOP. PERFORATED SQUEEZE HOLES @ 520', HURRICANE SERVICES ESTABLISHED CIRCULATION, AND MIXED & PUMPED 187 SXS 70/30 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 9/1/2009, 1:00 P.M. HURRICANE SERVICES TICKET #3386.

Perfs:

Top	Bot	Thru	Comments
2768	2771	CSG	
2739	2743	CSG	
2684	2687	CSG	

10-20-09
2010060415

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 17 2009


CONSERVATION DIVISION
WICHITA, KS

Remarks: GPS: LAT. 37.38828, LONG: -96.59525

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)