

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21870-00-00
Spot: NENW Sec/Twnshp/Rge: 35-28S-34W
660 feet from N Section Line, 1980 feet from W Section Line
Lease Name: SANTALA Well #: 12-C35-28-34
County: HASKELL Total Vertical Depth: 5660 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4110		WITH 2 SX CMT
CIBP		4507		
SURF	8.625	1843		WITH 800 SX CMT
PROD	5.5	4752	0	WITH 150 SX CMT

Well Type: QLOH UIC Docket No: _____ Date/Time to Plug: 08/28/2009 1:00 PM
Plug Co. License No.: 32721 Plug Co. Name: ELDRIDGE WELL SERVICE LLC
Proposal Rcvd. from: STEVE RIDENHOUR Company: PRESCO WESTERN Phone: (303) 444-8881

Proposed Plugging Method: SET CIBP @ 4110' WITH 2 SX CMT. PERFORATE CSG @ 1860' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE W/50 SX CMT.

183.95

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2009 4:30 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

CIBP @ 4110' WITH 2 SX CMT. PERFORATE 5 1/2" @ 1860'. TIED ONTO 5 1/2" & PUMPED 350 SX CMT W/GOOD CIRCULATION OUT ANNULUS. LOST CIRCULATION, 5 1/2" & ANNULUS WENT ON VACUUM. LET SET 20 MINUTES. PUMPED INTO 5 1/2" WITH 175 SX CMT, GOOD BLOW ON ANNULUS BUT NO CIRCULATION. RAN OUT OF CMT. SDON. 8/31/09: TAGGED TOC @ 86' FROM SURFACE. PUMPED 15 SX CMT INTO 5 1/2" & 30 SX CMT INTO ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4539	4549		SWOPE
4358	4367		IOLA
4164	4173		LANSING

10-20-09
2010060416

RECEIVED
SEP 21 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED

SEP 10 2009

KCC DODGE CITY

Signed

Jack MacClaskey
(TECHNICIAN)