

3-10 15-051-19245-00-01 81

4-041662

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 2-12-60

SW NW NW /4 SEC. 09, 12 S, 17 W  
4290 feet from S section line  
4950 feet from E section line

Operator license# 30946

Lease Roth-Rohleder well # 2

Operator: Lawrence Weilert

County Ellis

Address: 1700 E. 29th. Street  
Hays, Kansas 67601

Well total depth 3678 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 196 feet  
CWC.

119.54

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 10 Month: March Year: 95

Plugging proposal received from: Lawrence Weilert

Company: Lawrence Weilert Phone: \_\_\_\_\_

Were: 5 1/2" casing set at 3677' with cement. N.A. D.V. at 1397'  
circulate to surface with 600 sxs. cement. Perfs at 3400' to 3655'.  
W.L.M. 3600' - T.O.F. 900' estimate. Ordered 250 sxs. 60/40 posmix  
with 1/4# flocele - 10% gel - plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 10:30A.M. Day: 10 , Month: March , Year: 95

Actual plugging report: Hooked-up to 5 1/2" casing, squeezed down casing  
with 50 sxs. cement with 200# hulls, followed with 10 sxs. gel, followed  
with 150 sxs. cement with 200# hulls. Max. P.S.I. 400#. S.I.P. 100#.  
Cement to surface in 8 5/8" S.P.

3-20-1995

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES \_\_\_\_\_, CALC , NO \_\_\_\_\_ Dakota plug: YES , NO   
Plugged through TUBING \_\_\_\_\_, CASING . Elevation: \_\_\_\_\_ GL

I  did  did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

DATE 3-23-95  
WY. NO. 13440