

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 189-22575 - 0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 4/26/07

Well Operator: EOG RESOURCES, INC. KCC License #: 5278

Address: 3817 NW EXPRESSWAY, SUITE 500 City: OKLAHOMA CITY
(Owner / Company Name) (Operator's)

State: OK Zip Code: 73112-1483 Contact Phone: (405) 246 - 3100

Lease: MID-AMERICA CATTLE Well #: 14 #1 Sec. 14 Twp. 34 S. R. 38 East West

NW - NW - NE Spot Location / QQQQ County: STEVENS

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 1675' Cemented with: 670 Sacks

Production Casing Size: 5 1/2" Set at: 6747' Cemented with: 330 Sacks

List (ALL) Perforations and Bridgeplug Sets: 6535-6540', 6552-6562', CIBP 6500' & 6230', 6236-6245', 6247-6261', 6206-6222'

Elevation: 3186' (G.L. / K.B.) T.D.: 6750' PBTD: 6653' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): SET 5 1/2" CIBP @ 6156' W/2 SX, CUT/PULL CSG @ FREEPOINT, SET CMT PLGS @ 1725' W/100 SX, @ USEABLE WTR DEPTH W/50 SX, AND @ 50' TO SURF W/15 SX

OR PLUG PER KCC GUIDELINES & REGULATIONS

RECEIVED

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

OCT 23 2009

If not explain why? Submitted with ACO-1

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: CANDY DRISCOLL

Phone: (405) 246 - 3140

Address: 3817 NW EXPRESSWAY, SUITE 500 City / State: OKLAHOMA CITY, OK 73112-1483

Plugging Contractor: ORR ENTERPRISES KCC License #: 33338

Address: PO BOX 1706, DUNCAN, OK 73534 Phone: (580) 467 - 0258
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): UPON APPROVAL

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/22/09 Authorized Operator / Agent: Candy Driscoll (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Dust
PPT*



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

EOG RESOURCES, INC.
3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112-1483

October 26, 2009

Re: MID AMERICA CATTLE #14 1
API 15-189-22575-00-00
14-34S-38W, 330 FNL 2310 FEL
STEVENS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after April 24, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888