

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3273
Name: Herman Loeb LLC
Address 1: PO Box 838
Address 2: _____
City: Lawrenceville State: ILL Zip: 62439 + 0838
Contact Person: Ed Loeb
Phone: (618) 943-2227
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 5132 Bottom: 5144 T.D. 5263
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 199-20-067-00-00
Spot Description: NE-NE-SW/4
_____ Sec. 32 Twp. 15 S. R. 42 East West
2,310 Feet from North / South Line of Section
2,970 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Wallace
Lease Name: Bergquist A Well #: 2
Date Well Completed: 04/25/1986
The plugging proposal was approved on: 08/02/2009 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 08/03/2009
Plugging Completed: 08/03/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	388	none
		Production	4 1/2	5300	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing sanded in 4 1/2 production casing @ 3100'. Ran coiled tubing to 2950'. Pumped 347 sx cement & 300# hulls. Shut down for 3 hrs. Tagged cement @ 1330'. Ran tubing to 1320'. Pumped 51 sx cement & 50# hulls. Cement circulated to surface. Connected to 8 5/8 surface casing. Pumped 55 sx cement. Maximum pressure 160#. Witness Darrell Dipman. Plug complete Sanjel tkt#9150557

RECEIVED
AUG 20 2009

Plugging Contractor License #: 32997 34249 Name: Sanjel USA Inc. KCC WICHITA
Address 1: 200,505 2nd Street SW Address 2: _____
City: Calgary, Alberta State: Canada Zip: T2P1N8 + _____
Phone: (403) 269-1420
Name of Party Responsible for Plugging Fees: Herman Loeb
State of ILL County, _____, ss.
Shane Pelton Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

PKT