

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Brungardt Oil & Leasing, Inc.

Address: PO Box 871, Russell, KS 67665

Phone: (785) 483-4975 Operator License #: 3956

Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9-29-09 (Date)

by: Case Morris (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-23,814-00-00

Lease Name: Mayhew

Well Number: 1

Spot Location (QQQQ): _____ - NE - SW - SE SE

600 Feet from North / South Section Line

850 Feet from East / West Section Line

Sec. 30 Twp. 6 S. R. 18 East West

County: Rooks

Date Well Completed: 9-29-09

Plugging Commenced: 9-29-09

Plugging Completed: 9-29-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	219'	Cmtd. w/150 sax

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set:

Run drill pipe to 3,565', pump 25 sax cement thru drill pipe; run drill pipe to 1,575', pump 25 sax cement thru drill pipe; run drill pipe to 1,050', pump 100 sax cement thru drill pipe; run drill pipe to 275', pump 40 sax cement thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 30 sax cement down rat hole and 15 sax cement down mouse hole.

Name of Plugging Contractor: Shields Drilling Co. License #: 5184

Address: PO Box 709, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Brungardt Oil & Leasing, Inc.

State of KANSAS County, RUSSELL, ss.

Burton Beery Contractor
(Employer or Operator or Operator)

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Burton Beery

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED and SWORN TO before me, this 5th day of October, 2009

Ruth Phillips My Commission Expires: _____
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
OCT 15 2009
KCC WICHITA

Handwritten initials




Shields

Russell, Kansas

WELL LOG

Operator: Brungardt Oil & Leasing, Inc.
 Well: Mayhew #1
 Commenced: 9-22-09
 Completed: 9-29-09
 Contractor: Shields Drilling Co.

Well Description: 600' FSL, 850' FEL
 SE/4 Sec. 30-6S-18W
 Rooks Co., KS



CASING RECORD		
Size	Run	Pulled
8 5/8"	219'	Cmtd. w/150 sax

Elevation: 2,031' K.B.

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & shale	855'
Sand	1,265'
Sand & redbed	1,561'
Anhydrite	1,589'
Redbed & shale	2,010'
Shale	2,520'
Shale & lime	3,020'
Lime	3,584'
Arbuckle	3,635' RTD

RECEIVED
 OCT 15 2009
 KCC WICHITA

Notes