

WELL PLUGGING RECORD

OR
15-051-06574-00-00
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

523-524

County. Sec. 1 Twp. 11 Rge. (E) 17 (W)

If a producing well is abandoned, date of last production..... 193.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

This hole was filled with mud from 3621' to 250' where a cement plug was placed from 250' to 240'. The hole was filled from 240' to the top with mud, the casing was left in the hole and bull plugged. The top of the bull-plugged casing was covered with cement.

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? **YES**
Was exception made? **NO** If so describe.

Correspondence regarding this well should be addressed to.....**Twin Drilling Company**
Address.....**Box 1799, Tulsa, Oklahoma.**

STATE OF Kansas, COUNTY OF Ellis, ss.
I. C. T. Roberts, an (employee of owner XXXXXXXXXX) of the above described well

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

1707 Main St. Haverhill, Mass.

(Address)

SUBSCRIBED AND SWORN to before me this 24th day of March, 1938

My commission expires.

July 14, 1941

.....
Notary Public.

Location NW, SW, NE, of S. 1,
T. 12, R. 17, Ellis
Co., Kans.
Commenced 2-28-38
Total Depth 3621'

HALL #1

Company Twin Drilling Co.
Completed 3-24-38
Contractor Twin Drilling Co.

Casing Record: 15" - 30"



FORMATION	DEPTH	FORMATION	DEPTH
Shale & shells	40	Lime, light, medium	2866
Shale	180	Lime, light, broken	2894
Shale, dark	360	Shale, dark, medium	2914
Shale, sandy, shells	414	Lime, broken	2950
Shale, blue	440	Lime, gray, hard	2985
Sand	450	Lime	3000
Shale, blue, shells	520	Lime, grey, hard	3034
Sand	620	Lime, light, hard	3092
Shale, blue, shells	676	Lime, grey, black, iron, shells	3112
Shale, shelly	736	hard	3136
Sand, soft (Dakota)	834	Lime, light, hard	3165
Shale, blue, medium	864	Lime, light, medium	3205
Shale, sandy, medium	895	Lime, grey, medium	3235
Shale, medium	940	Lime, light	3243
Shale, blue, soft	995	Shale	3243
Shale, red, soft	1105	Top of Kansas City 3243	
Shale, blue, shells	1165	Lime, light, hard	3274
Shale, red	1185	Lime, light, medium	3277½
Lime (Anhydrite)	1231	Cored 3277½-86, recovered 7'	
Lime, broken	1240	Lime	3286
Shale, red, sticky	1254	Lime, light	3303
Shale, red, soft	1300	Lime, light, medium	3317
Shale, blue, soft	1348	Shale, lime, shells	3328
Shale, blue	1395	Lime, light, medium	3351
Shale, light	1410	Lime, light, hard	3382
Shale, light, sticky	1422	Lime, light	3415
Lime, light, broken	1428	Lime, light, hard	3440
Shale, lime shells	1446	Lime, light, medium	3473
Shale, grey, shells, sticky	1506	Base of Kansas City 3473	
Shale, blue, shelly	1590	Shale	3479
Shale, grey, shells	1693	Lime, broken	3504
Salt	1765	Shale,	3509
Lime, dark, shells	1791	Lime	3520
Shale, shelly	1811	Conglomerate	3577
Lime, light	1831	Lime (Siliceous)	3621
Lime, light, iron, shells	1853	Cored 3615-21, recovered 5' (no oil)	
Lime, light, broken, medium	1884	Top Sil. 3577.	
Cyp, iron, shells,	1926		
Lime, grey	1963		
Lime, grey, hard	1978		
Lime, broken, iron, shells	2008		
Lime, grey, medium	2022		
Shale, red, medium	2030		
Lime, light, hard	2062		
Lime, broken	2105		
Lime, light, hard	2168		
Lime, shale, iron	2203		
Lime, light, hard	2290		
Lime, light, medium	2377		
Shale, red	2385		
Lime, light, hard	2414		
Lime, light, medium	2459		
Lime, light, hard	2485		
Lime, light, medium	2528		
Lime, grey, medium	2613		
Lime, grey, hard	2621		
Lime, grey, medium	2661		
Lime, light, hard	2691		
Shale, blue	2696		
Lime, broken	2705		
Shale, grey, shells, medium	2714		
Lime, broken	2738		
Lime, grey, medium	2753		
Shale, blue, medium	2761		
Lime, light, medium	2773		
Shale, blue, medium	2790		
Lime, light, hard	2811		

I hereby certify that this is a true and correct copy of well log of the Hall #1 Well, located in the N. W. Corner of SW¼, of NE¼, of Section 1, Township 12, Range 17W, Ellis County, Kansas.

TWIN DRILLING COMPANY

By L. P. Proctor Supt.

Subscribed and sworn to before me, this 24th day of March, 1937.

Robt. B. Hamell
Notary Public.

My commission expires July 14, 1941.

