

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-051-00099-00-00  
WELL PLUGGING RECORD

Ellis County. Sec. 9 Twp. 12 Rge. (E) 17 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/C. SE

Lease Owner Glickman Oil Co. - Veeder Supply Co.

Lease Name Rohleder Well No. 1

Office Address 439 South St. Francis, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 7, 1952

Application for plugging filed February 7, 1952

Application for plugging approved February 7, 1952


Plugging commenced February 7, 1952

Plugging completed February 7, 1952

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3756 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	190'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 186' set plug with  $\frac{1}{2}$  sack of hulls and 15 sacks of cement. Filled hole with mud to 35' set plug with  $\frac{1}{2}$  sack of hulls and 10 sacks of cement.

2-10-1952

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Veeder Supply & Development Company

Address P. O. Box 201

Cherryvale, Kansas

STATE OF KANSAS, COUNTY OF MONTGOMERY, ss.

FLOYD W. HILD (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. THE VEEDER SUPPLY & DEVELOPMENT COMPANY

(Signature) Floyd W. Hild

Box 201, Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11th day of February, 1952

Olaf Larsson

Notary Public.

My commission expires July 11, 1952

23-8390-s 6-51-20M

PLUGGING  
FILE NO. 9 T 12 R 17 W  
BOOK 143 PAGE 19

15-051-00099-00-00

Company Glickman Oil Co. - Veeder Supply Co.

Sec. 9 T. 12 R. 17

Loc. SE/4

County Ellis County, Kansas

Farm Rohleder

No. 1

Total Depth 3756'

Comm. 1-25-52


Comp. 2-7-52

Shot or Treated

Contractor Veeder Supply Company Drilled with Rig - D

Issued No. of Days - 14

No. of Bits -



Casing

20 in. 10 in  
 15 1/2 81/4  
 12 1/2 65/8  
 13 3/8 53/16

Set 190' of 6-5/8" Casing Cemented with 125 sacks cement.

Elevation

Production

Figures Indicate Bottom of Formation

Cellar	0	9	9
Clay	9	20	11
Rock	20	35	15
Sand	35	40	5
Shale Shells Sand	40	65	25
Sand Shale Rock	65	150	85
Shale Rock	150	190	40
Shale	190	380	190
Shale Shells	380	560	180
Sand Shale	560	690	130
Sand	690	770	80
Shale Sand Iron	770	1015	245
Shale	1015	1040	25
Shale Red Bed	1040	1368	328
Anhydrite	1368	1407	39
Shale Shells	1407	1700	293
Salt Shale	1700	1730	30
Salt Shale Shells	1730	1980	250
Line Shale	1980	2125	145
Line Shale Shells	2125	2170	45
Line Shale	2170	3145	975
Line	3145	3659	514
Cherty Conglomerate	3659	3718	59
Arbuckle Line	3718	3756	38
Total Depth	3756'		

Plugged at 185 feet with 15 sacks cement  
 Plugged at 35' feet with 10 sacks cement

2-16-1952

