

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE NAME Roth - Rohlleder  
 WELL NUMBER 2  
4290 Ft. from S Section Line  
4950 Ft. from E Section Line  
 SEC. 9 TWP. 19 RGE. 17 (E) or (W)  
 COUNTY Pittsburg  
 Date Well Completed 2-12-60  
 Plugging Commenced 3-10-95  
 Plugging Completed 3-10-95

LEASE OPERATOR Lawrence Winkler  
 ADDRESS 1700 E. 29th St. Hays, Kansas 67601  
 PHONE# (913) 625-9528 OPERATORS LICENSE NO. 30946  
 Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-2-95 (date)  
 by Barbara L. Warner (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? -

Producing Formation Art Depth to Top 3667 Bottom 3671 T.D. 3678

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD


| Formation      | Content | From        | To          | Size         | Put In      | Pulled out  |
|----------------|---------|-------------|-------------|--------------|-------------|-------------|
| <u>LANE-KC</u> |         | <u>3400</u> | <u>3655</u> | <u>5 1/2</u> | <u>3677</u> | <u>None</u> |
|                |         |             |             | <u>8 5/8</u> | <u>196</u>  | <u>None</u> |
|                |         |             |             |              |             |             |
|                |         |             |             |              |             |             |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.  
D.V. @ 1397' w/ 600 SY amt circulated to surf. Hooked up to 5 1/2" casing.  
squeezed down casing with 50 SY amt of cement.  
10 SYs gel followed with 150 SYs amt w/ 200# Bulky Jet cement.  
MAX. 400# P.S.I. - S.I. 100# P.S.I. Cement at surf. in 8 5/8" S.P.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. 4-13-1915  
 Address Russell, Kansas STATE CORPORATION COMMISSION  
 APR 13 1995  
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lawrence Winkler  
 STATE OF Kansas COUNTY OF Pittsburg, ss. Barbara L. Warner

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Lawrence Winkler  
 (Address) 1700 E 29th St Hays, KS 67601



AND SWORN TO before me this 10TH day of APRIL, 1995

GREG KASPER  
 Notary Public

My Commission Expires: 7-12-98