


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County. Sec. 9 Twp. 12 Rge. 17 <sup>1/2</sup> (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NE SW NE  
Lease Owner Isern Brothers Et al  
Lease Name Dreiling "C" Well No. 1  
Office Address Box 45, Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 5, 1957 19  
Application for plugging filed September 5, 1957 19  
Application for plugging approved September 5, 1957 19  
Plugging commenced September 5, 1957 19  
Plugging completed September 5, 1957 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3715 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	<u>Surface Pipe</u>	<u>0</u>	<u>224'</u>	<u>8-5/8"</u>	<u>224'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 550'.  
Bridged hole at 550', ran 25 sacks  
cement through drill pipe 550' up.  
Bridged hole at 210', ran 25 sacks  
cement through drill pipe 210' up.  
Bridged hole at 35', ran 10 sacks  
cement. Plug 35' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
9-9-1957

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Isern Drilling Company  
Address Box 45, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON  
I, M. M. Shropshire (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Shropshire  
Lyons, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 19 57

My commission expires Feb. 10, 1959.

George A. Meyer  
Notary Public.

PLUGGING  
FILE SEC 9 T 12 R 17W  
BOOK PAGE 43 LINE 11

15-051-19244-00-00

WELL LOG

ISERN BROTHERS ET ALL, OWNER - DREILING C #1  
NE/4 SW/4 NE/4 Section 9, Township 12, Range 17 W,  
Ellis County, Kansas

ELEVATION: 2123 DF	Figures indicate bottom of formation:		
	0	to	530 shale & shells
			620 shale & sand
			750 sand
			815 shale & shells
			1025 sand
			1135 shale & shells
			1343 red rock
			1473 Anhydrite
			1985 shale & shells
			2740 lime & shale
			2890 shale & shells
			3625 lime & shale
			3655 lime
			3695 lime & chert
		3715 lime	
Rotary Commenced 8 - 26 - 57		3715 Rotary Total	
Completed 9 - 5 - 57		Depth D&A	

STATE OF KANSAS )  
COUNTY OF BARTON) SS

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first dully sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M M Shropshire

Subscribed and Sworn to before me this 6th day of September, 1957

George A Meyer  
Notary Public

My commission Expires Feb. 10, 1959

RECEIVED  
STATE CORPORATE RECORDS  
9-9-1957  
SEP 9 1957  
CONSERVATION DIVISION  
Michta, Kansas

PLUGGING			
FILE	SEC. 9	T. 12	R. 17W
BOOK	PAGE 43	LINE	11