


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-19244-00-01
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

ELLIS County. Sec. 9 Twp. 12S Rge. 17W (X) (W)
Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner PETROLEUM, INC.,
Lease Name DREILING "G" Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed SEPTEMBER 20 19 64
Application for plugging filed SEPTEMBER 20 19 64
Application for plugging approved SEPTEMBER 20 19 64
Plugging commenced SEPTEMBER 20 19 64
Plugging completed SEPTEMBER 20, 19 64
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation - - - Depth to top - - Bottom - - Total Depth of Well 3715 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	224'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDERED UP WITH HEAVY MUD TO 540', FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ONTO PLUG. MUDDERED UP WITH HEAVY MUD TO 200', FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ONTO PLUG. MUDDERED UP WITH HEAVY MUD TO 40', FOLLOWED BY WOODEN PLUG AND 10 SACKS CEMENT TO BASE OF WELL CELLAR. PLUGGED RAT HOLE WITH 2 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

10-5-1964
OCT 5 - 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) MONTE CHADD, DIST. PROD. SUPT.

ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 1ST day of OCTOBER, 19 64

My commission expires APRIL 14, 1967

Notary Public.

WELL LOG

15-051-19244-00-01

COMPANY Petroleum, Inc.

SEC. 9 T. 12S R. 17W

FARM Dreiling

NO. "G" #1 (W./D.)

LOC. NE SW NE

TOTAL DEPTH 3715'


COUNTY Ellis

COMM. Sept. 16, 1964

COMP. Sept. 20, 1964

CONTRACTOR Garvey Drilling Co.

CASING 8 5/8" @ 224'



ELEVATION 2125 KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Petroleum, Inc. moved in and washed down the # 1 Dreiling which was originally drilled by Isern Drilling Company in Sept. of 1957. There was a Schlumberger Log ran on the original well. Petroleum, Inc. ran three straddle DST's with negative results and plugged the well.

Log Tops

Anhydrite	1340 (+ 785)
Heebner	3308 (-1183)
Toronto	3330 (-1205)
Lansing	3355 (-1230)
Arbuckle	3616 (-1491)
Log T. D.	3715 (-1590)

RECEIVED
STATE CORPORATION COMMISSION
10-5-1964
OCT 5 - 1964
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company
upon oath state the above and foregoing is a true and correct copy of the log of the Dreiling "G" #1 (W./D.) well.

Sam N. Stephens

Subscribed and sworn to before me this 30th day of September 19 64

My Commission Expires: April 14th, 1963

Arthur J. Miles
NOTARY PUBLIC