

15-051-30268-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

ELLIS

County, Sec. 9 Twp. 12S Rge. 17 (X) W (W)

Location as "NE/CNW/SW" or footage from lines N/2 NW SW

Lease Owner ISERN-WELLS

Lease Name ROHLER Well No. 1

Office Address P. O. BOX 486, ELLINWOOD, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed APRIL 9, 19 66

Application for plugging filed APRIL 9, 19 66

Application for plugging approved APRIL 9, 19 66

Plugging commenced APRIL 9, 19 66

Plugging completed APRIL 9, 19 66

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO F MASSEY

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3725 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	179.02	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED WITH HEAVY MUD TO 540'. SET PLUG. PUT IN 20 SX CEMENT. FILLED WITH HEAVY MUD TO 174'. SET PLUG. PUT IN 20 SX CEMENT. FILLED WITH HEAVY MUD UP TO 40'. SET PLUG. FILLED TO TOP WITH 1/2 SX HULLS AND 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

4-14-1966
APR 14 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING COMPANY
Address 107 RULE BUILDING, WICHITA, KANSAS 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. GALLOWAY

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
G. F. GALLOWAY 107 RULE BUILDING
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of APRIL, 19 66

Vicky Jacobs
VICKY JACOBS Notary Public.



15-051-30268-00-00

WELL LOG

OPERATOR: ISERN-WELLS C. W. FINE, JR.

WELL NAME: ROHLER #1 LOCATION: N/2 NW SW 9-12S-17W

COUNTY: ELLIS STATE: KANSAS

WELL COMMENCED: APRIL 1, 1966 WELL COMPLETED: APRIL 9, 1966

ELEVATION: 2134 KB TOTAL DEPTH: 3725 RTD

PRODUCTION: DRY & ABANDONED RIG NO: #2

CASING - 8-5/8": 8 JTS, 179.02' W/150 SX QUIKSET CEMENT

5-1/2": _____

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	845	SHALE & SAND		
845	1050	SAND	3/4°	1000'
1050	1270	RED BED & SHALE	1°	1500'
1270	1360	RED BED	1-3/4°	2000'
1360	1395	ANHYDRITE		
1395	1890	SHALE & SHELLS	1-1/4°	2250'
1890	3360	LIME & SHALE	3/4°	2500' DST #1
3360	3670	LIME	1/2°	3458- 3490'
3670	3725	CONGLOMERATE		

RECEIVED
STATE CORPORATION COMMISSION
4-14-1966
APR 14 1966
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.
By J. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 12th day of APRIL, 1966.

My comm. exp: May 20, 1967

Vicky Jacobs
Vicky Jacobs - Notary Public

