

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

15-051-00489-00-00

WELL PLUGGING RECORD

Ellis County, Sec. 9 Twp. 12S Rge. 17W (E) (W)

Location as "NE/CNWxSWx" or footage from lines SE NW SW

Lease Owner Carl Lebsack

Lease Name Rohleder Well No. 1

Office Address 406 S. Ash - Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed February 1 19 55

Application for plugging approved 19

Plugging commenced February 7 19 55

Plugging completed February 10 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3704 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	180'	None
				5-1/2"	3520'	2950'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The cement inside the pipe was drilled to 3520' and casing was perforated from 3486' to 3490'. Filled hole with sand from 3520' to 3470' and ran 4 sacks of cement. Mudded hole to 180', set a 10' rock bridge and ran 15 sacks of cement. Mudded hole to top and ran 10 sacks of cement. Plugging completed.

2-23-1955

Name of Plugging Contractor West Supply Co., Inc. (If additional description is necessary, use BACK of this sheet)  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss. Carl Lebsack (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Lebsack

(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of February, 19 55

My commission expires June 10, 1957

Notary Public.

PLUGGING  
FILE SEC 9 T 12 R 17W  
BOOK PAGE 24 LINE 37

15-051-00489-00-00

WELL LOG

Carl Lobsack et al, Owner - Rohleder #1  
SE/4 NW/4 SW/4 Section 9, Township 12, Range 17W,  
Ellis County, Kansas

ELEVATION: 2141 DF

Figures indicate bottom of formation

0	to	100	post rock
		650	shale & shells
		780	sand
		890	shale & shells
		1010	sand
		1050	shale & shells
		1354	Red bed
		1385	Anhydrite
		1760	shale & shells
		1950	salt
		1985	shale & shells
		2820	lime & shale
		3000	shale & shells
		3195	lime & shale
		3704	lime
		3704	Total Rotary Depth

PIPE RECORD:

8-5/8" set at 180'

5-1/2" set at 3520'

Rotary Commenced 10-4-54  
Completed 10-13-54

STATE OF KANSAS )  
COUNTY OF BARTON ) ss

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 15th day of October, 1954.

George A. Meyer

Notary Public  
**RECEIVED**  
STATE CORPORATION COMMISSION  
2-21-1955  
FEB 21 1955

My commission expires Feb. 10, 1955.

CONSERVATION DIVISION  
Wichita, Kansas