


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-00259-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 9 Twp. 12 Rge. 17W (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Bennett & Roberts Oil Operations
Lease Name J. P. Roth Well No. 1
Office Address Drawer 633, Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7/26 19 53
Application for plugging filed 4/22 19 57
Application for plugging approved 4/24 19 57
Plugging commenced 4/26 19 57
Plugging completed 4/30 19 57

Reason for abandonment of well or producing formation Not enough oil to produce economically

If a producing well is abandoned, date of last production 4/1X 4/19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well # Eldon Petty
Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3675 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	197'	None
				5 1/2"	3648 1/2'	3303'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock to 3630', dumped

4 sax cement @ 3630' w/dump bailer. Top of ce-

ment, 3600'. Filled hole with mud to 220', set

rock bridge, dumped 20 sax cement. Top of cement,

160'. Filled hole with mud to 35', set rock

bridge, dumped 10 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co.
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1957

My commission expires 6/17/58

Clara Hummel
Notary Public.

PLUGGING
FILE SEC 9 12 17W
BOOK PAGE 8 20

5-7-1957

15-051-00259-00-00

Bennett & Roberts Drilling Co.
J. P. Roth #1

NW NW NW 9-12-17W
Ellis County, Ks.

Commencement Date 6/28/53
Rotary Completion Date 7/10/53
Cable Tool Completion Date 7/27/53
RTD: 3650(-1514)
Cable Tool TD: 3675
8 5/8" casing set @ 197' w/145 sx cmt.
5 1/2" casing set @ 3648 1/2' w/50 sx cmt.

	Tops:
Topeka Lime	3095(- 959)
Heebner Shale	3330(-1194)
Toronto Lime	3352(-1216)
Lansing K.C.	3377(-1241)
Basal K.C.	3607(-1471)
Marmaton	3615(-1479)
Simpson Shale	3634(-1498)
Simpson Sand	3645(-1509)
Arbuckle Dolomite	3648(-1512)

Formations:	Depth:
Soil	15'
Post rock clay	30
Sand	35
Pat rock clay	100
Post rock shale	197
Shale	521
Sand	612
Shale	641
Red Bed	700
Shale, shells & Sand	1275
Sandy Shale & Pyrite	1350
Shale & Shells	1360
Anhydrite	1420
Red Bed Shale	1650
Shale & Shells	1880
Lime & Shale	2140
Lime & shale streaks of pyrite	2273
Lime & Shale	2510
Lime, shale streaks	2580
Lime & Shale	3070
Shale	3110
Lime	3155
Lime & Shale	3170
Lime & streaks of shale	3215
Shale & Lime	3250
Lime	3350
Lime & Shale	3387
Lime	3425
Lime & Shale streaks	3470
Lime & Shale	3650
Lime & Shale	3675

STATE OF KANSAS)
RUSSELL COUNTY) SS

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By *J. P. Roth*

Subscribed and sworn to before me this 14th day of July, 1953.

Clara Hummel
Notary Public

My commission expires 6/17/54

PLUGGING
FILE SEC. <u>9</u> T. <u>12</u> R. <u>17W</u>
BOOK PAGE <u>8</u> LINE <u>20</u>

RECEIVED
STATE CORPORATION COMMISSION
4-24-1957
APR 24 1957
CONSERVATION DIVISION
Wichita, Kansas